



Complexities in flood modelling and mitigation for large infrastructure projects – Rosanna level crossing removal

Elizabeth Smolinska, Senior Water Engineer

Stormwater Victoria 2019 Conference, Marysville

JACOBS®

www.jacobs.com | worldwide


Presentation content

- Context – Why this topic?
 - Significant Infrastructure boom
 - Flood modelling and mitigation a key element of these projects
- The Project
 - NEPA: North Eastern Program Alliance
- My Role
- Challenges
 - Technical modelling
 - Coordination
 - Communication
- Lessons learnt/advice
- Conclusions and wrap up



The Project

- NEPA – North Eastern Program Alliance
- Upgrades to the Hurstbridge line



The Project




- Level crossing removal at Grange Rd, Alphington
- Track duplication between Heidelberg & Rosanna
- Level crossing removal at Lower Plenty Road, Rosanna
- Substation upgrades



My role on the project

- Flood Lead
 - Point of call for all flood related works across the project
- What were we trying to achieve?
 - No impact
 - No loss of floodplain storage
 - Climate Change and Blockage assessments
- Main responsibilities
 - Modelling work
 - Internal communication and coordination
 - External stakeholder coordination and approvals




The project area in detail

- Existing flooding issues at Rosanna
- Level crossing removal at Lower Plenty Road and construction of new Rosanna Station




Challenges – base case model

- Hydrology and Hydraulics – RORB and TUFLOW
- Working with an established model
- Establishment of a Base Case model
 - Review and rebuild of model needed
 - Greater model refinement needed around the areas of interest
 - Discussions with Melbourne Water and original consultant
 - Taking an unapproved model to an approved model
 - Project Timelines



Challenges – coordination

- Alphington, Heidelberg and Rosanna
- Coordination with a number of disciplines
 - Civil Roads, Rail, Drainage, Carparks, Bridges, Geotechnical, Architecture, Landscape Architecture, Environmental, Substations
- Various points of contact for each site
- Internal and External
- Coordination of inputs
 - Data formats, alignment of dates
- 4 Design Stages for submissions:
 - Preliminary, Detailed, Final & Issued for Construction
- Constantly changing and evolving design
- Staying ahead of the game



- A large number of stakeholders
 - Melbourne Water, Local Council, LXRA, MTM, VicRoads
- Inception meetings
- Stakeholder Comment Review Sheets
- Closing out stakeholder comments
- Collaborative approach within the design team
- Ongoing meetings to resolve specific issues
- Finding the balance in mitigation solutions

JACOBS®

Challenges – specific modelling issues

- Cutting down the Rosanna model to obtain WSE for forecourt
- Modelling of detailed features, e.g. wombat crossings
- Modelling of WSUD assets where they perform a dual flooding function
- IDO's – integrated development opportunities
- Timing of flows and discharges into MW assets – negotiations
- Modelling of areas or items that would have otherwise never required flood modelling



Wrap Up

- Infrastructure boom
- The Project – NEPA, upgrades along the Hurstbridge lin
- Challenges:
 - Establishing a base case and approved model
 - Multi-disciplinary coordination
 - Internal and external contacts, varying for each site
 - Various design stages
 - Project timelines
 - External stakeholder liaison
 - Finding the balance in mitigation solutions
- For flood modelling and mitigation:
 - Get in early! Stay ahead of the game
 - Communicate
 - Drive the design outcomes you want



Time-lapse

Questions?

Thank you!

JACOBS®

www.jacobs.com | worldwide